

*Bill Patnode*

◆ EXCAVATION ◆



**SITES • UTILITIES • ROADS  
LAND CLEARING • MULCH MOWING  
SEPTIC SYSTEMS INSTALLED & REPAIRED**

O: 603-399-9966  
C: 603-313-5184  
E: bpdign@yahoo.com

708 Glebe Road  
Westmoreland, NH 03467

September 25, 2021

Town of Gilsum  
PO Box 36  
650 Route 10  
Gilsum, NH 03448

Proposal too include:

- Move in all required equipment
- Chop all trees in gravel cut areas
- Pile all brush
- Pile all junk wood
- Salvage wood goes to contractor
- Stump all gravel cut areas
- Pile stumps onsite
- Remove gravel roadway and place over slopes
- Remove center gravel area and move over slope
- Grade out gravel over slopes and compact
- Purchase approximately clay
- Place clay over slopes and grade
- Place clay over top if land fill area and grade
- Hydro seed all clay areas approximately 94,725 square fee

Scope of work:

- Areas to be chopped and stumped:
  - Side entry road
  - Center island
- Areas to cut fill material:

Side entry road

Center island

Areas to be filled and graded:

Base of slopes approximately 21,000 square feet

Areas to be Clay covered 94,725 square feet

Areas to be seeded approximately 94,725 square feet

Items not covered by proposal:

Remove guard rail posts

Disposal of my scrap wood

Town to supply dumpster for any existing garbage on site

Payment schedule:

Start of job \$25,000.00

Upon delivery of clay \$25,000.00

Job completion \$24,700.00

\$74,700.00

Total for project: